

## QUOTATION

To:	Tasleeh General Trading Abu Dhabi, UAE Mob: +971 54 746 4656	Date	: 12-Nov-2025
Attn:	Mr. Nicolas, <a href="mailto:mep@tasleeh.ae">E: mep@tasleeh.ae</a>	Qtn. Ref. #	: BFME 1131 Rev 05

Subject : Installation of Sports flooring

Project : Barakah

Dear Mr. Nicolas,

Thank you for showing interest in our product. Further to your inquiry, please find below our best price for the required works.

	Product Description	Qty	Price (AED)	Total Amount (AED)
	<b>SCOPE OF WORKS :</b>			
1	<b>Installation of Sports Flooring</b> <b>Application System : Polyurethane Flooring</b> <b>Total Thickness : 45mm</b>  <b>Scope of work:</b> Applying the adhesive on the concrete floor. Laying Rubber Tile of 43mm thick on the straight line towards the entire floor. Apply Pore Filler Part A & B Component to fill the voids and joints on the fixed rubber tiles. Applying self-level coating to level the entire floor. Applying Indoor Special Topcoat as finish coat on the surface.	320 m <sup>2</sup>	105.00	33,600.00
2	<b>Walls</b> * Installation of GI Stud * Installation of Rubber	290 m <sup>2</sup>	100.00	29,000.00
3	<b>Ceiling</b> * Installation of Metal Plates * Installation of GI Stud * Installation of Rubber	320 m <sup>2</sup>	100.00	32,000.00
Note :	<ul style="list-style-type: none"> <li>Accommodation, food and transportation are included in our price.</li> <li>All the required materials to be provided by the client.</li> </ul>			
<b>Total Value :</b>				<b>94,600.00</b>

5% VAT will be applicable on above mentioned prices.

#### General Site Conditions:

- This quote is Re-measurable.
- The floor should be clean, hard, sufficiently level and dry to start the installation works.
- Civil works of any sort are not part of our proposal.
- Lighting, Water & electricity should be provided at the site free of cost to us.
- A safe storage space should be provided at site for our tools and materials.
- Dumping bins are to be supplied at site by the client/main contractor.
- Site should be free from other trades.
- Installed flooring must be allowed adequate bonding time. Use of trolleys and wheeled traffic must be avoided during the first week after installation. All cement-based products such as self-levelling compounds achieve their full compressive strength in 28 days only. Care must be given during this time to avoid pointed loads to be placed over the flooring. In case such furniture to be placed in during this time, please provide protective boards so that the impact load will not cause indentation over the floor.
- Floor Box, Floor protection, trims and accessories are not included in our prices unless stated.
- Shop drawings when required can be provided @ extra rates.
- Order once placed with the manufacturer cannot be cancelled or altered.
- Prices quoted above are linked to specific quantity and changes in quantity may affect the price.

#### Terms and Conditions:

##### Payment

: 55% advance upon order confirmation, 15% upon completion of walls installation, 15% upon completion of the ceiling installations and 15% upon completion of flooring works

##### Validity

: 7 days.

Thanking you,  
For Bloomsford Middle East LLC  
Simran Sharma